

85

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac

Located In:

Corner Code #

1. Public Land Survey

T 43N R 8W      33

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Aug 29 1995

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner common to Sections 2-11. Corner recorded in 1968 by Billy D. Buckler, RLS: "This corner reestablished midway and on line between two Sec. corners. No evidence of original corner. Corner lies 120' north of truck trail. 1" pipe with 4" aluminum cap. 9" Hard Maple S75N 13.2".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) Recovered Buckler's monument as described, in good condition, and at record bearing and distance from the remains of the 9" Hard Maple witness, now cut down. Determined that the monument had been placed at an erroneous position in 1968: 17.4' South and 6.57' West of the position described in Section A above. Removed the monument and reestablished the corner on a straight line between Section corners 2675.99' east and west, being the proportionate position. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. aluminum tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Set 1" pipe with 4" MOHR cap.  
Blazed, scribed, and set measuring nails  
in the following new bearing trees:  
6" J. Pine N54W-24.9'      1/4S MBT  
8" W. Pine N32E 81.0'  
3" J. Pine East 35.8'  
10" R. Pine S25W 88.4'  
Bearings are magnetic. Placed a  
location poster on a cedar post about  
180' south, on north side of a road.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 11-28-95

For the Michigan Department of Natural Resources - Forest Management Division