

84

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 8W	I2
	T 43N R 8W	I3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I3 Aug 29 1995
I2 Aug 28 1995

I, Stephan J. Szyzkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3				●	2	1		
3									●				
4		7	8	9	10					11	12		
5													
6		10	11	12	13					14	13		
7													
8		19	20	21	22					23	24		
9													
10		30	29	28	27					26	25		
11													
12		31	32	33	34					35	36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I2) Quarter corner common to Sections 2-3. Corner recorded in 1968 by Billy D. Buckler, RLS: "This corner re-established by proportionate measure between an original corner, 1/2 mile South and a Section corner 1/2 mile North. Set 1" Pipe with 4" aluminum cap. 14" Red Pine N57E 93.5', 9" Soft Maple S35N 5.7'".

(I3) Corner common to Sections 2-3-10-11. Corner restored at the original position in 1968 by Billy D. Buckler, RLS. Placed 1" pipe with 4" aluminum cap and the following NBTs: 6" Cedar N33E 12.2', 10" Cedar S20W 12.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I2) Found Buckler's monument at record bearing and distance from the remaining 1968 witness Jack Pine. Determined the monument to have been placed at an erroneous position in 1968: 12.6' West and 45.3' North of the position described in Section A above. I removed the monument and reestablished the corner on a straight line between the Section corner 2686.15' South and Section corner 2705.63' North, being proportionate to the original record. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

(I3) Found Buckler's monument as described, in good condition, and at record bearing and distance from his 1968 witnesses, both in good condition. Left the monument in place, marked new top blazes on the 1968 trees, marked two new witnesses, and set measuring nails in all.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I2) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

8" Cherry S71W 21.2' "1/4S NBT"
8" W. Pine N42W 33.05' "
3" J. Pine N14W 34.7' "
5" W. Pine N08E 36.65' "

Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.

(I3) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

8" Cedar N33E 12.55'
12" Cedar S20W 12.5'
6" Cedar S58W 15.05'
4" Cedar N13W 5.05'

A 3" squared and scribed cedar post was found adjacent. Bearings are magnetic.



Signed by Stephan J. Szyzkoski
Surveyor's Michigan License No. 33986

Date 11-28-95

For the Michigan Department of Natural Resources - Forest Management Division