

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>8W</u>	E <u>5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jul 07 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5				●								
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


(E5) Corner common to Sections 8-9-16-17. Corner reestablished by single proportionate measurement in 1968 by Billy D. Buckler, RLS. 1.25" x 30" iron pipe, buried in center of road. 6" Cedar S42E 69.2', 28" W. Pine stump N60W 81.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E5) Recovered the 1968 monument, as described, in good condition, buried 2.5' below the road's surface. Recovered the two 1968 witnesses at record bearing and distance. Placed 1" ID iron pipe capped with a yellow plastic cap stamped "MICH DNR PS33986" on top of the 1968 monument. The cap is now at the road's surface. The centerline of the road is now approx. 2' west of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E5) Set 1" pipe with plastic cap. Blazed, scribed, and set measuring nails in the following:
 6" W. Birch S75W 41.45' "S17 NBT"
 8" W. Birch N54W 42.3' "S8 NBT"
 6" W. Birch N78E 31.8' "S9 NBT"
 The 1968 wits:
 10" Cedar S41E 69.5' "S16 NBT"
 28" W. Pine stump N60W 81.4'
 Bearings are magnetic. Distances to nail/tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/29/00

For the Michigan Department of Natural Resources - Forest Management Division