

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>43NR</u>	<u>8W</u>	<u>D5</u>
	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
2. Property Controlling in Section	S	_____	_____	_____
	S	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	_____	_____
	S	_____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Feb 15 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (D5) Quarter corner common to Sections 8-17. Reestablished "midway and on line between two section corners" in 1968 by Billy D. Buckler, RLS. 1" pipe with 4" aluminum cap. 7" Balsam S50E 34.1', 6" 8.Spruce S82E 56.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(D5) Recovered the 1968 monument, as described, in good condition, and at record bearing and distance from the 1968 8.Spruce NBT. The Balsam NBT is now dead and gone. Left the monument in place and marked four new accessories as described below. The corner lies on the east edge of an alder river bottom.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (D5) Found 1" pipe with 4" alum. cap.

Blazed, scribed, and set measuring nails in the following:

4" W. Birch N42E 7.5'	"1/4S NBT"
6" Spruce N80E 14.0'	do
6" W. Birch S48E 23.4'	do
5" W. Birch S30W 42.65'	do

Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/3/00

For the Michigan Department of Natural Resources - Forest Management Division