

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>8W</u>	<u>A3</u>
	T <u>43N</u> R <u>8W</u>	<u>B3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 20 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3	•											
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A3) Corner common to Sections 6-7 T43N-R08W and Sections 1-12 T43N-R09W. 1969 - Remonumented by Billy D. Buckler: This corner replaced as recorded by Marcus Schaaf, RLS. 5/8" iron pin buried in center of E-W road. 8" W.Birch S20W 53.9', 7" Aspen N18W 56.4'.
 (B3) Quarter corner common to Sections 6-7. 1968 - Remonumented by Billy D. Buckler RLS: This corner replaced as set by D.A. Brotherton, Land Surveyor in 1916. Set 1" pipe with 4" aluminum cap. 11" Y.Birch S24W 29.6', 7" Y.Birch S31E 46.8', Concrete project marker S87W 36.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A3) Recovered and accepted the 1969 monument in good condition, buried in the centerline of an E-W blacktop road, 2" below the surface. The NBT W.Birch is dead but standing at record bearing and distance. The NBT Aspen was not recovered. Left the monument in place, placed a yellow plastic cap on it, and made new witnesses as described below.
 (B3) Recovered the 1968 monument in good condition and at record bearing and distance from the 1968 witnesses. The NBT Y.Birch SW is in good condition with overgrown blazes, the Y.Birch SE is a stump, the concrete project marker is in good condition. The Hemlock stump with witness marks, noted in the 1968 record, has no discernible markings left. Centerline of Hiawatha Trail is 39' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A3) Found 5/8" iron pin. Placed plastic cap on it. Set measuring nails with plastic tags in:
 12" Spruce S40E 73.3' mrkd "S7 NBT"
 8" W.Birch S07E 55.4' mrkd do
 6" W.Birch S40W 66.0' mrkd "S12 NBT"
 Power pole EN2/85/107 S16W 34.4'
 Bearings are magnetic. Distances are to nail with tag.

(B3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails with plastic tags in:
 20" Y.Birch S31W 29.75' mrkd "1/4S"
 5" Spruce S18E 10.15'
 Measured to the following:
 5' high plastic UG cable post N75E 53.9'
 Sign post CoRd 832 N14E 105.8'
 Conc. proj. marker S87W 36.1'
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/26/04