

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac

(County)

Located In:

Corner Code #

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>43N</u> R <u>8W</u>                  | <u>A5</u>   |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>7</u> T <u>43N</u> R <u>8W</u>       | <u>12</u>   |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

12 Oct 18 2004  
 A5 Oct 20 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(A5) Corner common to Sections 7-18 T43N-R08W and 12-13 T43N-R09W. 1840 - Established by Wm A. Burt: Set post. Beech 7 N22W 34 links, Hemlock 22 N61W 4 links. 1845 - Notes of T43N-R08W subdivision by H. Brevoort: Beech 4 N1E 27, Beech 20 S28E 37. 1849 - Notes of T43N-R09W subdivision by W. Ives: [west] between 12 and 13 ... 4.68 Hemlock 15. 1962 - Monumented by Billy D. Buckler RLS. Set 1" pipe with 4" aluminum cap. 5" R.Pine S25E 03 links, 6" J.Pine N63E 16 links, 7" J.Pine S86W 9.5 links. Method of restoration was not noted. Pencil entry by unknown person in GLO field notebook copy at MDNR office in Newberry states " at 80.60 on rand from S. Intersect Cor 4.15 East of post. Hem. stump; Beech NW down & hole SE. Also Hem. line tree 4.65 west. Found Aug. 25, 1933" (12-Sec. 7) South 1/16 corner, Sec. 7. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(A5) Recovered the 1962 monument in good condition and at record bearing and distance from the NBTs R.Pine SE, in good condition, and the J.Pine SW, standing dead. Accepted same as the best available evidence of the position of the original corner. Mr. Buckler's record does not state that this position is a perpetuation of the 1933 position described above but the undersigned presumes that it is. Left the monument in place and made new witnesses.

(12-Sec. 7) Established the corner midway and on a straight line between Center of Section 1319.93' north and Quarter corner 1319.93' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(A5) Found 1" ID 1. pipe with 4" alum. MDNR cap. Set measuring nails w/tags in the following marked trees:

- 12" R.Pine S26E 2.0' \*
- 12" R.Pine N13E 6.3' "S7 NBT"
- 12" R.Pine N69E 32.6' do
- 10" R.Pine S36W 23.85' "S13 NBT"

Bearings are magnetic. Distances are to nail with tag. \* denotes 1962 NBT.

(12) Set 1" IDx36" I. pipe with 4" alum.

MDNR cap. Set measuring nails with tags in the following marked trees:

- 6" Maple in clump N08W 21.5' "S1/16 BT"
- 5" Spruce N32E 8.75' do
- 7" Spruce S37E 22.0' do
- 12" Maple S69W 24.65' do

Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/26/04