

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>43N</u> R <u>8W</u> | <u>C4</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u>7</u> T <u>43N</u> R <u>8W</u> | <u>10</u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 18 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5	●											
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (C4) Quarter corner common to Sections 7-8. 1845 - Established by H. Brevoort: North between Sections 7&8 ...40.00 Set quarter section post. Balsam 6 N40W 12, Balsam 6 S35W 08. ... 80.00 Set post corner Section 5-6-7-8.
 (10-Sec. 7) South 1/16 corner between Section 7 T43N-R08W and Section 12 T43N-R09W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (C4) The original post and accessories were not recovered. Reestablished the corner midway and on line between Section corners 2647.91' north and south.
 (10-Sec. 7) Established the corner midway and on line between Quarter corner 1316.91' north and Section corner 1316.91' south. The corner lies about 14' south of an E-W trail and about 52' west of westerly edge of a spruce plantation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (C4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with tags in the following marked trees:
18" Cedar N79W 12.85' "1/4S NBT"
10" Cedar N32E 23.9' do
10" Cedar S66E 28.05' do
10" Cedar East 43.8' do
Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with tags in the following marked trees:
8" R.Pine S52W 9.45' "S1/16 BT"
8" R.Pine S80E 33.1' do
10" R.Pine West 55.55' do
12" Spruce N49W 95.9' do
Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/26/04