

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	43N	R	8W	B4
	T	43N	R	8W	A4
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Oct 18 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	●	●	8	9	10	11	12					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(B4) Center of Section 7. Not established in the original survey.

(A4) Quarter corner common to Section 7 T43N-R08W and Section 12 T43N-R09W. 1840 - Established by Wm.A.Burt: South on East side of Sec. 12 (T43N-R09W) ...40.00 Set qr. Section post. Hemlock 9 N73W 9 links, Birch 18 S17W 16 links ... 80.00 Set post corner secs. 12&13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(A4) The original post and accessories were not recovered. Reestablished the corner midway and on a line between Section corners 2633.81' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B4) Set 1"IDx36" 1.pipe with 4" alum. MDNR cap. Set measuring nails with tags in the following marked trees:

5" Balsam S36E 10.15' "CS BT"
 5" Balsam N04E 32.2' do
 3" Balsam N65E 11.4' do
 3" Maple S22E 3.7' do

Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(A4) Set 5/8"x18" rebar w/plastic cap "MICH DNR PS33986". Set measuring nails with tags in the following:

8" Maple N66E 22.15' "1/4S NBT"
 6" Maple S55E 16.7' do
 12" Maple N03W 27.3' do
 12" Maple S50W 3.65' do

squared and scribed a 6" Maple S70E 0.75' to center of tree. Bearings are magnetic. Distances are to nail with tag.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/26/04

