

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|------------|--------------------------|----------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S <u>5</u> | T <u>43N</u> R <u>8W</u> | <u>1</u> |
| | S | T R | _____ |
| 3. Miscellaneous Property in Sec. | S | T R | _____ |
| | S | T R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 28 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													


A. Description of original monument and accessories and/or subsequent restoration:
 (1-Sec. 5) West 1/16 corner on the north line of Section 5. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 5) Established the corner midway between closing corners C1 and D1 and on the township line defined by the standard corners of record. From the corner thus established, the center of an E-W road is North, 73 feet distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (1) Set 1" ID I. pipe with plastic cap "MICH DNR PS33986". Set measuring nails with tags in:
- 10" W. Birch S36W 40.3' mrdk "N1/16 BT"
- 8" Cherry N33E 106.5' do
- Cor. fnc post E-W-S S10E 59.7'
- Cor. fnce post N-N N10E 106.5'
- 1" pipe with DNR cap at Cor. #15 Sec.
- 32, T44N-R08W is West, 12.04'. The north rail of the RR is South 3.6'.



Stephan J. Szyszkoski

Signed by _____
 Surveyor's Michigan License No. 33986

Date 12/7/04