

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>8W</u>	<u>E4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>9</u> T <u>43N</u> R <u>8W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 24 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E4) Quarter corner common to Sections 8-9. 1968 - Corner reestablished by Billy D. Buckler RLS "by single proportionate measure to North and South and on the alignment of a North and South Road". Set 1.25"x30" iron pipe driven in center of road. 10" Soft Maple S78W 102.1', 6" Cedar N49E 46.7'
 (3-Sec. 9) North 1/16 corner between Sections 8 and 9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E4) The 1968 monument was not recovered and has apparently been destroyed by road construction. Recovered the 1968 witness trees and found that their horizontal position does not precisely conform to the record. Since I could not determine which of the two NBTs might be most reliable for the purposes of reestablishing the 1968 corner position, I reestablished the corner midway between Section corners 2610.20' north and south and at a weighted mean best fit with the 1968 record to the NBTs. The distances from the reestablished corner to the 1968 NBTs is 101.5' to the Maple notch (102.1' R) and 46.3' to the Cedar notch (46.7' R). This results in the reestablished corner being 4.93' west of a straight line between adjacent section corners and 1.5' West of the current center of a N-S road.
 (3-Sec. 9) Established the corner midway and on line between Section corner 1305.10' north and Quarter corner 1305.10' south. The position thus established falls 8' east of the center of a N-S road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E4) Set 5/8" x 24" rebar with plastic cap stamped MICH DNR PS33986 in road.	(3) Set 5/8" x 24" rebar with plastic cap stamped MICH DNR PS33986. Set measuring nails in:
Set measuring nails in:	
9" Cedar N57E 46.4' mrkd "1/4S" *	8" Spruce N44W 74.0' mrkd "N1/16 BT"
11" Cedar S81E 36.26' mrkd "1/4S NBT"	5" Cedar N56E 34.92' do
8" twin Cedar S49E 59.75' do	4" Maple S62E 37.6' do
6" triple W.Birch S61W 60.9' do	4" W.Birch S60W 61.2' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1968 NBT.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/6/07

For the Michigan Department of Natural Resources, Office of Land and Facilities

