

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>8W</u>	<u>F4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>9</u> T <u>43N</u> R <u>8W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Apr 24 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (F4) Center of Section 9. Not established in the original survey.
- (9-Sec. 9) East 1/16 corner, Section 9. Not established in the original survey.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (9-Sec. 9) Established the corner midway and on a straight line between Center of Section 1313.38' west and Quarter corner 1313.38' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (F4) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>10" Cedar N58W 8.25'    mrkd "CS BT"<br>9" Cedar N05W 12.35'    do<br>9" Cedar N77E 8.6'    do<br>6" Cedar S68E 17.17'    do<br>Bearings are magnetic. Distances are to<br>nail with tag. | (9) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>7" Cedar N67E 15.3'    mrkd "E1/16 BT"<br>7" Cedar S18E 15.62'    do<br>5" Cedar S72W 9.23'    do<br>6" Cedar N30W 8.4'    do<br>Bearings are magnetic. Distances are to<br>nail with tag. |
|--|--|

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/6/07

For the Michigan Department of Natural Resources, Office of Land and Facilities