

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 9 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 23-24-25-26

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7-31-64 with Forestry Aide Burnis

WITNESSES TO CORNER..... 6" Cedar (S 25 NBT), S 40° E, 33 Lks.



6" Cedar (S 24 NBT), N 72° E, 21 Lks.

5" Cedar (S 23 NBT), N 42° W, 37 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement, to Section Corners 1 mile to East, North and South and 1/4 Corner 1/2 mile to West. Blaze on Stump to NW facing corner. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 12/8/1964
REGISTERED LAND SURVEYOR