

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 9W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 25-26-35-36

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/30/64 with Forestry Aide Burnis

WITNESSES TO CORNER..... 8" Cedar (S 26 NBT), N 61° W, 14 1/2 Lks.



9" Cedar (S 25 NBT), N 23° E, 46 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement between Section Corner to North, Meander Corner to South, Woodpost and Lake to East and Lake to West. No Original Evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 12/8/1964
REGISTERED LAND SURVEYOR