

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

6 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		8A-Sec.25, 11A-Sec.25 11-Sec.25, 12-Sec.25 13-Sec.25, 13A-Sec.25
2. PROPERTY CONTROLLING IN SECTION <u>25</u> T. <u>43</u> N. S., R. <u>9</u> E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-27 & 7-11, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 8A-Sec.25 1/32 Corner, West of the West 1/16 Corner.
- 11A-Sec.25 1/32 Corner, West of SW 1/16 Corner.
- 11-Sec.25 South-West 1/16 Corner of Section 25.
- 12-Sec.25 South 1/16 Corner of Section 25.
- 13-Sec.25 South-East 1/16 Corner of Section 25.
- 13A-Sec.25 Meander Corner, East of the SE 1/16 Corner on shore of Lake Michigan.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8A-Sec.25 Placed corner midway between two corners.
- 11A-Sec.25 Placed corner midway between two corners.
- 11-Sec.25 Placed corner at center of SW 1/4 Section. Corner lies 60' West of Stream.
- 12-Sec.25 Placed corner midway between Center Corner to North and 1/4 Corner to South.
- 13-Sec.25 Placed corner at center of the SE 1/4 Section.
- 13A-Sec.25 Placed corner on the South 1/16 line, at West shore of Lake Michigan.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at all corners. Bearings are:
- 8A-Sec.25 6" Cedar, N25°E, 9.9' & 8" Cedar, West, 11.6' & 12" Cedar, S39°W, 24.6'.
 - 11A-Sec.25 14" Cedar, N45°W, 25.2' & 12" Cedar, S43°W, 17.9' & 6" Cedar, N33°E, 14.3'.
 - 11-Sec.25 6" Tam., S63°E, 11.9' & 6" Tam., S68°W, 27.7' & 12" H. Maple, N40°W, 19.5'.
 - 12-Sec.25 7" Spruce, S34°E, 20.7' & 7" Cedar, N28°W, 51.4' & 8" Cedar, S77°W, 28.3'.
 - 13-Sec.25 14" Cedar, N18°E, 6.0' & 8" Cedar, S24°E, 5.05' & 8" Cedar, S34°W, 2.23'.
 - 13A-Sec.25 6" W. Pine, N32°W, 47.1' & 8" Cedar, N81°W, 66.8' & 6" Cedar, S65°W, 55.25' & Large Boulder, S48°W, 20.0'.

SIGNED BY Billy D. Buckler DATE 11-2-79
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____