

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. E. R. <u>9</u> W.	<u>L-11, L-11A</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-15, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-11 Quarter Corner between Section's, 25-36, set by Wm Ives, D.S. in 1849. Bearings were: Y. Birch 12", S60°W, 15 lks. & Y. Birch 8", N22°E, 18 lks.
- L-11A Meander Corner between Section's, 25-36, on shore of Lake Michigan. Bearings were: Cedar 8", N65°W, 82 lks. and Cedar 4", S3°W, 32 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-11 Placed corner at wood post set by unknown surveyor. Distance checks well with other corner
- L-11A Placed Meander Corner by extending section line thru the 1/4 corner from West, Average Distance = 1,458.8'. Record Distance = 1,460.0'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminum cap at both corners. New Bearings:

- L-11 6" Cedar, N15°W, 63.9' and 8" Spruce, SW, 54.6'.
- L-11A 8" Cedar, N18°W, 45.0' & 10" Spruce, S56°W, 14.8' & 12" Spruce, S45°E, 30.9'. Corner lies 30' West of Lake Michigan timber line.

SIGNED BY Billy D. Buckler

DATE 11-9-79

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

