

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970
MACKINAC CO. 3 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. R. <u>8</u> E. W.	<u>A-12, E-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>44</u> N. R. <u>8</u> E. W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-17-85, 6-19, 7-16, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-12 West 1/4 Corner of Section 31. Tam. 4, S24°W, 9 lks. & W. Birch 4, N42°W 4 lks.
E-13 S.E. Section Corner of Section 32. Ironwood 7, N74°E, 17 lks & Sugar 15, N48°W, 30 lks.
2 East 1/16 Corner on North side of Section 36. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-12 Corner set M.P.O.L. between N.E. Section corner and the S.E. Section corner of Sec. 36.
E-13 Re-placed corner as set by Larry Feindt L.S. in 1974.
2 Corner set M.P.O.L. between N 1/4 Corner and N.E. Section Corner of Section 36.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- A-12 DNR Mont. 2 DNR Mont.
8" W. Pine, N50°E, 35.2' 6" W. Birch, N32°W, 19.05'
8" W. Pine, S73°E, 9.25' 3" Maple, S79°E, 29.05'
6" W. Pine, S15°W, 15.5' 6" Balsam, S65°E, 8.95'
4" W. Birch, N12°E, 17.1' 12" Balsam, S62°W, 13.8'
- E13 1" Pipe W/Plastic RLS Cap at corner. 1" Pipe W/Plastic RLS Cap Sec. Cor. 5-4, T43N R8W, is 15.84' East of this Section Corner. DNR Mont., S45°W, 33.0' & DNR Mont., N45°W, 33.0' & Stop Sign, S20°E, 37.2'.

SIGNED BY

Gerald L. Wiggins

DATE 9-22-86

Gerald L. Wiggins
SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: