

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

4 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> ^{N.} / _{S.} , R. <u>8</u> ^{E.} / _{W.}	<u>M-12, C-13, L-11</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>44</u> ^{N.} / _{S.} , R. <u>8</u> ^{E.} / _{W.}	<u>9</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-16-85, 7-2, 9-17, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-12 East 1/4 Corner of Section 36. OBT'S: 6" Tam., S45°W, 9 lks. & 14" Tam., N32°W, 18 lks.
 C-13 S.W. Sec. Cor. of Section 32. OBT'S: Sugar 16, N80°E, 24 lks. & Sugar 9, N46°W, 5 lks.
 L-11 North 1/4 Cor. of Section 36. Cor set by Billy D. Buckler L.S. 1969. 8" Tam., N35°E, 5.6' & 3" Cedar, S40°E, 5.3'.
 9 East 1/16 Corner of Section 36. Not Prev. Set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-12 Corner set at 2" Pipe set by Marus Schaaf R.L.S. Found remains of Tam. BT N32°W. 18 lks.
 C-13 Corner set by single proportionate measure between SW Cor. of Sec. 31. and SE Cor. of Sec. 32. Fence line runs north.
 L-11 Re-witnessed corner as set by Billy D. Buckler R.L.S. 3-2/-69.

- 9 Cor. set M.P.O.L. between East 1/4 Cor. and computed Center Cor. of Sec. 36. Found 1 1/2" pipe at center cor. to be 1.18' West and 9.82' South of computed center.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|------|------------------------------------|------|------------------------------|
| M-12 | DNR & 2" Pipe | L-11 | DNR placed over 1 1/2" pipe. |
| | 24" W. Pine, N76°W, 37.60' | | 6" Cedar, S44°E, 5.3' |
| | 6" Tam., N70°E, 12.60' | | 12" Tamarack, N37°E, 5.6' |
| | 8" Cedar, N17°E, 30.70' | | 10" Tamarack, S26°W, 32.1' |
| | 8" Cedar, N36°W, 39.05' | | 4" Cedar, N37°W, 8.75' |
| C-13 | DNR Mont. | 9 | DNR Mont. |
| | R.R. Track, South, 8.67' | | 4" Maple, S14°E, 7.3' |
| | DNR Mont. for Sec's. 6-5, T43N R8W | | 10" Maple, S18°W, 33.85' |
| | East 14.56' | | 8" Maple, West, 22.45' |
| | 10" Cherry, N2°W, 112.9' | | 12" Maple, N31°E, 14.6' |
| | 6" Aspen, N32°E, 121.2' | | |

SIGNED BY Gerald L. Wiggins
 Gerald L. Wiggins
 SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

DATE 9-22-86

