

35

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T 43N R 9W	K7
	T 43N R 9W	L7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jan 08 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(K7) Corner common to Sections 13-14-23-24. Corner perpetuated at a local position in 1962 by Billy D. Buckler, RLS: "This corner was established in intersection of fire lines in all four directions. Found no evidence of original corner but believe fire lines were located by Marcus Schaaf, Registered Land Surveyor. Corner monument 1" pipe with 4" aluminum cap (buried). Witnesses to corner, 6" Y. Birch N66W 82 links, 6" Hard Maple S39E 56 links".

(L7) Quarter corner common to Sections 13-24. Corner established in 1849 by William Ives: "40.00 set quarter section post. White Birch 10 N55E 13, Fir 10 SSE 08". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Recovered the 1962 monument, as described, a 1" ID iron pipe capped with a 4" dia. Michigan Dept. of Conservation tablet, in good condition, buried in the intersection of fire lines, and at record bearing and distance from both of Buckler's 1962 NBT's, found in good condition. Re-marked the top blaze on the 1962 witnesses, and marked two new accessories as described below. Corner recovered and re-witnessed by T.Stark, Newberry District Office.

(L7) Original post and accessories were not recovered. I found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between monumented section corners 2679.00' east and west. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDR tablet, appropriately stamped. The center of an E-W trail is 23.5' south of the corner monumented. Corner placed and witnessed by T.Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Found buried 1" iron pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails in the following:
8" Y. Birch N60W 59.9' "S14"
10" Maple S32E 37.2' "S24"
10" Beach S38W 28.5' "S23 NBT"
6" Maple N58E 31.2' "S13 NBT"
Bearings are magnetic. Placed location post S40E approx. 33'.

(L7) Set 1" pipe with 4" MDR cap. Blazed, scribed, and set measuring nails in the following:
5" Balsam N72W 11.1' "1/4S NBT"
4" Balsam N08W 9.9' "1/4S NBT"
16" Maple S80E 51.0' "1/4S NBT"
4" Twin Cherry S17W 9.15' "1/4S NBT"
Placed a 4" cedar fence post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 4-15-98

For the Michigan Department of Natural Resources - Forest Management Division