

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~42-43~~ NR. 10 W. . .

----- Mackinac -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 3-4-33-34 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 10" W. Pine ----- S 16° E ----- 22 links -----
"S 3 NBT"

12" Soft Maple ----- N 7° W ----- 43 links -----
"S 33 NBT"

10" Cedar ----- N 88° E ----- 48½ links -----
"S 34 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from four B.T.s.

Found white pine stump bearing S 87° W 32 links. Blaze, notch and overgrowth in poor condition. White pine bearing N 44° E 22 links down and in poor condition. Jack pine bearing S 62° W 67 links. B.T. and notch plain, good condition. Jack pine bearing S 63° E 70 links, trace of notch remains.

Distance checks 5 links north to stream.

Corner found while searching for corners in area with Jim Halbach, District Forester.

Found several lines in area run by Jackson, Reg. Surveyor, St. Ignace.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 7/17/57