

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T42-43 NR 10 W

Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 5-32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	<u>13" W. Pine</u>	<u>N 65° E</u>	<u>65 links</u>
		<u>"1/4 S NBT"</u>	
	<u>9" Cedar</u>	<u>S 36° W</u>	<u>19 links</u>
		<u>"1/4 S NBT"</u>	
	<u>10" Cedar</u>	<u>N 17° W</u>	<u>20 links</u>
		<u>"1/4 S NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from one 3" tamarack B.T. bearing N 80° E 35 links.  
B.T. broken off and shattered. Scribing "1/4 S" very plain.

Found by Forestry Division Survey Crew.

Found no evidence of use. 1/4 corner lies in swamp.

Corner placed and witnessed January 14, 1958.

SURVEYORS SEAL

SIGNED

*Billy D. Ruckler*  
REGISTERED LAND SURVEYOR

DATE 1/21/58