

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 42-43 NR 10 W

Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 4-5-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	<u>14" Red Pine</u>	<u>S 13° E</u>	<u>128 links</u>
		<u>"S 4 NBT"</u>	
	<u>15" Red Pine</u>	<u>S 41° W</u>	<u>123 links</u>
		<u>"S 5 NBT"</u>	
	<u>16" Red Pine</u>	<u>N 1° E</u>	<u>150 links</u>
		<u>"S 33 NBT"</u>	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by single proportionate measure east and west along township line using section corner 1 mile east and 1/4 corner 1/2 mile west.

No evidence of original corner.

Corner placed and witnessed January 14, 1958.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 1/14/58