

MAR 20 2000

Filing Requirement of Act 74, Mich. P.A. 1970  
Mackinac County Remonumentation Corner

SECTION

For corners in

<u>Mackinac</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>10W</u>	<u>C-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

**RECEIVED & FILED**  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 30 1999

AM \_\_\_\_\_ PM \_\_\_\_\_  
7 8 9 10 11 12 1 2 3 4 5 6

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on July 13, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7		8		9		10				12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

T43N R10W

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
(C-9) Section Corner Common to Sections 19, 20, 29 & 30, Township 43 North, Range 10 West.  
 1849 William Ives D.S. set post. Cedar 10 S60°W 22 White Birch 12 N53°E 12.  
 1980 John Smallwood, P.S. 16944 (MDOT) found a 1/2" iron in monument box and recorded in Liber B, Page 178 of the Mackinac County Corner Records.  
 1993 Gary Koepke, P.S. 26458 (MDOT) found a 1/2" iron in monument box and recorded in Liber D, Page 192 of Mackinac County Corner Records.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(C-9) Section Corner Common to Sections 19, 20, 29 & 30, Township 43 North, Range 10 West.  
 Found 5/8" iron with no cap in monument box. Accepted corner position as found. Corner was to be destroyed during road construction of U.S. 2 and was re-witnessed prior to construction.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(C-9) Section Corner Common to Sections 19, 20, 29 & 30, Township 43 North, Range 10 West.  
 After road construction set 1/2" iron with 3" stamped aluminum Mackinac County Remonumentation Corner cap in monument box. Road stationing MDOT plans dated 7/21/97 is 28+852.46.

Witnesses:

Poplar 10"	N15°W	231.52 feet
Power Pole	N20°E	110.33 feet
Poplar 6"	S50°E	141.07 feet
White Birch 4"	S35°W	73.56 feet

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-05-99 *WEL*



Signed by William L. Karr Date 12/16/99

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995