

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Mackinac <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 20 T 43N R 10W	13
	S 20 T 43N R 10W	9
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 9 09/24/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (13-Sec. 20) Southeast 1/16 corner, Section 20. Not established in the original survey.
- (9-Sec. 20) East 1/16 corner, Section 20. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (13-Sec. 20) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (9-Sec. 20) Established the corner midway and on a straight line between Center of Section 20 1318.34' west and Quarter corner 1318.34' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| <p>(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br/>         11" Cedar S72E 15.35'                      mrkd "SE1/16 BT"<br/>         8" Cedar N41E 27.15'                      do<br/>         14" Cedar N12W 23.45'                      do<br/>         7" Cedar S59W 23.75'                      do<br/>         Bearings are magnetic.</p> | <p>(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br/>         5" Cedar N64W 3.7'                      mrkd "E1/16 BT"<br/>         6" Cedar N26E 11.75'                      do<br/>         9" Cedar S63E 7.72'                      do<br/>         4" Cedar S17W 5.54'                      do<br/>         Bearings are magnetic.</p> |
|--|--|

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/13/2009

