

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T <u>43N</u> R <u>10W</u>	<u>14</u>
	S <u>20</u> T <u>43N</u> R <u>10W</u>	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 12 09/24/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 20) South 1/16 between Sections 20 and 21. Not established in the original survey.

(12-Sec. 20) South 1/16 corner, Section 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 20) Established the corner midway and on the Section line between Section corner 1313.91' south and Quarter corner 1313.91' north. The position for the corner falls in the traveled surface of Hwy M-117 and was not monumented. Established a witness corner at the intersection of the South E W 1/16 line with the westerly R/W line of M-117 74.77' west of the corner position.

(12-Sec. 20) Established the corner midway and on a straight line between Quarter corner 1312.45' south and Center of Section 20 1312.45' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap stamped "WC S1/16 20/21 74.77' East"
 Set measuring nail with MDNR tag in the side of:
 6" Cedar N01E 2.6' mrkd "WC BT"
 8" Cedar N60W 25.95' do
 5" Cedar S51W 5.05' do
 5" Tamarack S45E 14.35' do
 Bearings are magnetic.

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 6" Cedar S27W 5.65' mrkd "S1/16 BT"
 7" Cedar West 35.7' do
 6" Tamarack North 7.6' do
 5" Spruce S43E 21.58' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/13/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

