

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T <u>43N</u> R <u>10W</u>	<u>8</u>
	S <u>20</u> T <u>43N</u> R <u>10W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 1 07/01/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 20) West 1/16 corner, Section 20. Not established in the original survey.
- (1-Sec. 20) West 1/16 corner between Sections 17 and 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 20) Established the corner midway and on a straight line between Quarter corner 1313.47' west and Center of Section 20 1313.47' east. The position for the corner falls in an E-W gravel road.
- (1-Sec. 20) Established the corner midway and on the Section line between Section corner 1328.93' west and Quarter corner 1328.93' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <ul style="list-style-type: none"> (8) Set 5/8"x18" rebar with plastic MDNR cap 6" below gravel surface of road. Chis. "+" in east edge on top of large rock S55E 49.5' Power pole 'EN4,58' N62W 93.2' nail/tag 8" crab apple N72E 88.25' do SE cor. garage N34W 77.9' Bearings are magnetic. | <ul style="list-style-type: none"> (1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 9" R.Pine N63W 16.7' mrkd "W1/16 BT" 7" R.Pine N13E 15.35' do 7" R.Pine N84E 13.0' do 6" R.Pine S26E 14.6' do Bearings are magnetic. |
|---|---|

Signed by Stephan J. Szyszkoski Date 10/13/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities



47278
47279