

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>X</u> , R. <u>11</u> W. <u>X</u>	E-7, E-8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____, S. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____, S. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David L. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-15, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 7 Sec. Cor. 16-17-20-21. Cedar 8", S39°W, 19 lks. & Cedar 9", N64°E, 20 lks. and Wood Post at cor.
- 8 1/4 Cor. on East side of Section 20. Wood Post, Spruce 5", S40°W, 20 lks. & Cedar 5", N33°E, 4 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7 Set in center line of N-S road and in line with a very old fence remains west. This also places the position of the N1/16 cor. on the east line of sec. 20 in line with an old fence west. This occupation shows on an aerial mosaic of this twp. dated 1930. I therefore accept the position of the fence line and the center of road as being the best available evidence of the true position of the sec. cor.
- 8 Cor. set M.P.O.L. between NE sec. cor. and SE sec. cor. of sec. 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|-----|-------------------------|
| -7 1" pipe buried in center line of road. | E-8 | 1" pipe. New Bearings: |
| New Bearings: | | |
| 7' Tamarack, N31°E, 75.3' | | 7" Cedar, N38°W, 99.6' |
| 8' Cedar, S39°W, 79.0' | | 8" Cedar, N83°W, 64.6' |
| 6' Cedar, S72°W, 75.0' | | 16" Cedar, S45°W, 96.3' |
| 8' Cedar, S58°E, 41.1' | | 8" Cedar, N86°E, 28.2' |

SIGNED BY

David B. Babbitt

David B. Babbitt

DATE 8-3-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: