

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLL-18 _____ ING IN SECTION _____	T. 43 N. _____ E. _____ S., R. 11 W. _____	1, 15
3. MISCELLANEOUS _____ PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-17, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- West 1/16 corner on the North Section Line of Section 18. Not previously established.
- 5 West 1/16 corner on the South Section Line of Section 18. Not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Set by single proportionate between the North 1/4 cor. and the N.W. Sec. Cor. of Sec. 18.
- 5 Set M.P.O.L. between the South 1/4 cor. and the S.W. Sec. Cor. of Sec. 18. (G.L.O. record shows this sec. line as 80.00 chs.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument. Bearings:

5" Tamarack, N35^oE, 30.8'
6" Tamarack, N57^oW, 78.6'
4" Tamarack, S68^oW, 40.4'
4" Tamarack, S19^oE, 50.4'

15 D.N.R. Monument. Bearings:

8" R. Maple, S27^oW, 33.7'
4" Cedar, N39^oW, 53.7'
6" Cedar, N03^oW, 72.0'
8" Cedar, N47^oE, 93.8'

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 4-21-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: