

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Mackinac Co. 2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>43</u> N. <u>11</u> <del>S.</del> W.		E-5, B-7
2. PROPERTY CONTROLLING IN SECTION_____ T. _____ N. _____ E. _____ S., R. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION_____ T. _____ N. _____ E. _____ S., R. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**REGISTER OF DEEDS STAMP AND FILING NUMBER**

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-17, 19 82, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 5 North 1/4 cor. of sec. 18. Wood Post, Spruce 6", N58°W, 11 lks. & Tam6", S55°E, 23 lks.
- 7 South 1/4 cor. of sec. 18. Wood Post, Fir 4", N50°E, 16 lks. & Fir 6", South, 32 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 Set by single proportion to G.L.O. record between the N.W. and N.E. sec. cors. of sec. 18.
- 7 Set M.P.O.L. between the S.E. and S.W. sec. cors. of sec. 18. (G.L.O. record shows this mile as 80.00 chs.) No sign of OBT'S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                                   |                                    |
|-----------------------------------|------------------------------------|
| -5 D.N.R. Monument. New Bearings: | B-7 D.N.R. Monument. New Bearings: |
| 10" W. Pine, N64°E, 159.2'        | 4" Cedar, S09°W, 34.5'             |
| 8" W. Pine, N80°E, 194.9'         | 6" Cedar, S20°E, 23.3'             |
| 10" W. Pine, N28°W, 67.7'         | 8" Cedar, S77°E, 55.1'             |

Corner lies in open march.

SIGNED BY David E. Babbitt DATE 4-21-82  
 David E. Babbitt  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)  
 FOR STATE AND UNITED STATES AGENCIES: