

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970  
Mackinac Co. 2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>43</u> N. <u>X</u> , R. <u>11</u> E. <u>X</u> W. _____		C-7, C-6
2. PROPERTY CONTROLL- ING IN SECTION _____, T. _____ N. _____ E. _____ S., R. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ E. _____ S., R. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-17, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 7 S.W. Sec. Cor. of Sec. 17. Wood Post, Spruce 6", S59°W, 61 lks. & Spruce 3", N38°E, 76 lks.
- 6 East 1/4 Cor. of Sec. 18. Wood Post, Tam. 3", S81°E, 33 lks. & Spruce 2", N46°W, 25 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7 Found stub of Tam. Line Tree with all hour notches plain, recorded as being 499.62' South of this sec. cor. Measure distance from the line tree to the N.W cor. of sec. 17 is almost exactly the same as recorded in the G.L.O. notes. Set this sec. cor. on line between the line tree and the N.W sec. cor. of sec. 17 with distance proportion to G.L.O. record.
- 6 Set M.P.O.L. between the N.E. and S.E. sec. cors. of sec. 18. No sign of OET'S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 7 D.N.R. Monument. New Bearings: C-6 D.N.R. Monument.  
 4" Tamarack, S17°E, 73.5' Corner lies in open marsh. No suitable  
 4" Tamarack, N69°E, 36.0' witnesses available.  
 4" Tamarack, N02°W, 61.6'

SIGNED BY

David E. Babbitt  
David E. Babbitt

DATE 4-21-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)