

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

2 Corners.

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>43</u> N. <u>8.</u> R. <u>11</u> E. <u>W.</u> | C-13, E-11 |
| 2. PROPERTY CONTROLLING IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-14 & 4-15, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-13 Southeast corner of section 31. Wood Post, OETS Fir 9", N67°E, 19 lks. & Cedar 9", N21°W, 14 lks.
- B-11 1/4 corner on north side of section 31. Wood Post, OETS Y. Birch 5", S58°W, 41 lks. Y. Birch 5", N50°E, 45 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-13 Set in line with center line of roads north and east. This position fits well with a recorded sec. cor. one mile west and with occupied lines north, east, and south. No other evidence found. Therefore the center lines of these roads was accepted as the best available evidence of the sec. cor. position.
- B-11 Set on line bet. the NE and NW sec. cors. of sec. 31 and in line with a very old fence line north and south. This position agrees well with occupied lines in the plat of Corrine.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13 1" pipe W/plastic RLS cap buried in road. Bearings: 12" Spruce, S20°E, 93.5' & 10" Spruce, S41°W, 47.5' & 6" Cedar, S86°W, 53.2' & 10" Aspen, N60°W, 35.9'.
- E-11 1" pipe W/plastic RLS cap. Bearings: Fence Corner, North, 43.75' & Power Pole, S84°W, 118.92' & Center Line of E-W Road, North, 13.2'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 8-18-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: