

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. R. <u>11</u> E. W.	C-11
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	T. <u>43</u> N. R. <u>11</u> E. W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-15, 19 83, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-11 Northeast corner of section 31. Wood Post, OETS Beech 12", S60°W, 8 lks, and Beech 6", N30°E, 35 lks. Soo Line R.R. plans show tie to sec. cor, but no description of a cor. mon. Plat of Corrine also shows a tie but to description of the monument.
- 8 West 1/16 corner of section 31, Not prev. set. on the E-W 1/4 line of sec. 31.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Set according to ties shown on the Soo Line R.R. ROW plans from R.R. mons found on the east line of sec. 30 and in the plat of Corrine. None of the original plat mons. in the plat of Corrine were found but this position agrees well with the lot lines as occupied at this time.
- 8 Corner set by proportionate measurement on line betw. the west 1/4 corner and the center corner of sec. 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-11 3/8" pipe set at corner. Bearings: Fence Corner, S33°E, 28.95' & Power Pole, S81°W, 147.28' & Center Line E-W Road, North, 7.1', Large Iron Bar (R.R. ROW Mon.), North, 420.3'.
- 8 DNR Monument. Bearings: 10" Cedar, N53°W, 25.7' & 8" Cedar, N29°W, 9.3' & 7" Cedar, N86°E, 16.2' & 6" Cedar, S28°W, 18.8'.

SIGNED BY David E. Babbitt  
David E. Babbitt

DATE 8-18-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)