

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>11</u> E. <u>W.</u>	<u>B-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	T. <u>43</u> N. <u>11</u> E. <u>W.</u>	<u>5</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-18, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B-13 South 1/4 corner of section 31. Wood Post. OBTS Tamarack 9", N32°E, 8 lks.  
Spruce 5", N66°W, 13 lks.

5 North 1/16 corner of section 31. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-13 Corner set by single proportionate measure between SW and SE section corners of sec. 31.

5 Corner set M.P.O.L. between North 1/4 corner and Center corner of section 31.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR monument set at both corners. Bearings:

B-13	6" Cedar, S11°W, 4.2'	5	8" Aspen, S79°W, 11.5'
	8" Cedar, N65°W, 10.4'		6" Aspen, N39°W, 16.2'
	8" Cedar, N3°W, 9.0'		7" Aspen, N52°E, 16.5'
	7" Cedar, S72°E, 11.4'		8" Aspen, S89°E, 27.8'

SIGNED BY

David B. Babbitt  
David B. Babbitt

DATE 8-18-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)