

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

2 Corners

Mackinac Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. S., R. <u>12</u> E. W.	<u>L-1, K-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-17, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-1 North 1/4 Corner of Section 1. G. A. Shadko R.L.S. 1934 found 3/4" Iron Pipe for 1/4 Cor. in 1955. No wit. found or established.
- K-3 S.W. Section Corner of Section 1. Corner set by Wilcox, Erickson & Assoc. 6-7-73. Wit. S15°W, 27.12', 6" Maple, S55°W, 63.49', 8" Db1. Cedar, N20°W, 66.13', 6" Pine, a 1/2" Iron and Cap was placed at corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-1 No pipe found. Re-established by re-tracing G. A. Shadko's 1955 survey for a "Public Fishing Site" (No. 49-5).
- K-3 Could not find Wilcox, Erickson & Assoc. Iron Rod and only one of their N.B.T.'S remains Found their S½ and S.W. Sec. Cor. of Sec. 2 and re-established this corner by re-tracing their survey for the south line of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" pipe w/plastic R.L.S. Cap placed at both corners. Bearings:
- L-1 Corner set in ditch line, 6" Maple, N2°E, 45.85' & Power Pole, S85°W, 54.8' & 10" W. Birch, South, 37.65', 8" Twin Maple, S50°E, 51.8' (Tags in Trees).
- K-3 Buried in South edge of road. 8" Aspen, N5°W, 40.65' & 6" W. Birch, S1°E, 34.05' 10" Maple, S56°W, 56.5' & Wilcox's Cedar, S61°W, 61.4'.

SIGNED BY

*David B. Babbitt*

David B. Babbitt

DATE 5-14-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)