

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

4 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> R. <u>12</u> <sup>E.</sup> / <sub>W.</sub>	<u>J-7A, J-9</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> R. <u>12</u> <sup>E.</sup> / <sub>W.</sub>	<u>9, 13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> / <sub>S.</sub> R. _____ <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-27, 6-25, 7-2, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- J-7A Meander Corner North side of Sec. 23. OBT'S: Spruce 8, S72°E, 42 lks. & Spruce 8, N23°E, 25 lks.
- J-9 South 1/4 Cor. of Sec. 23. OBT'S: Fir 8, N60°E, 21 lks. & Fir 8, S35°W, 18 lks.
- 9 East 1/16 Corner of Section 23. Not prev. set.
- 13 Southeast 1/16 Corner of Section 23. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- J-7A Corner set on North Line of Section 23 on East edge of Browns Lake.
- J-9 Corner set M.P.O.L. between the SW Sec. Cor. and the SE Sec. Cor. of Sec. 23. Measurements compare well with Highway Dep't. plans.
- 9 Corner set M.P.O.L. between East 1/4 Corner and Center Corner of Section 23.
- 13 Corner set at Center of S.E. 1/4 of Section 23 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: DNR MONUMENTS EXCEPT J-9

- |   |                           |
|---|---------------------------|
| J-7A 5" Cedar, N26°E, 11.3'               | 9 4" Cedar, N24°W, 2.0'   |
| 5" Cedar, N51°E, 12.1'                    | 8" Cedar, N41°W, 14.9'    |
| 6" Cedar, East, 35.5'                     | 6" Cedar, S80°W, 13.7'    |
| 7" Cedar, N36°W, 14.5'                    | 8" Cedar, S35°W, 9.1'     |
| J-9 1" pipe W/plastic cap.                | 13 12" Cedar, N9°E, 13.7' |
| Tag/Nail in 3" W. Birch, S79°E, 47.4'     | 6" Cedar, N54°E, 2.2'     |
| Tag/Nail in 10" Twin Cedar, S46°E, 13.15' | 12" Cedar, S62°E, 8.4'    |
| Tag/Nail in Power Pole, West, 49.25'      | 10" B. Ash, S89°W, 6.45'  |
| R.O.W. Marker, N10°E, 18.73'              |                           |

SIGNED BY Gerald L. Wiggins DATE 9-10-86

Gerald L. Wiggins  
SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: