

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

4 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. R. 12 W.	K-2A
2. PROPERTY CONTROLLING IN SECTION 2	T. 43 N. R. 12 W.	16, 13, 13-9
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-18, 6-2, 6-4, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-2A Meander Corner on East side of Section 2. OBT'S: Tam. 7, S32°W, 126 lks & Tam. 8, S15°E, 71 lks.
- 16 East 1/16 Corner on South side of Section 2. Not prev. set.
- 13 S.E. 1/16 Corner of Section 2. Not prev. set.
- 13-9 Meander Corner 1172.96' North of the S.E. 1/16 Corner of Section 2. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-2A Corner set at record distance from S.E. corner of Section 2 on a mean bearing between the West line of Section 2 and the East line of Section 1.
- 16 Corner set M.P.O.L. between S.E. Section Corner and South 1/4 Corner of Section 2.
- 13 Corner set at the Center of the S.E. 1/4 of Section 2 by closed traverse.
- 13-9 Corner set on the West line of Gov't. Lot 1 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: DNR MONUMENTS

- | | | | | |
|------|---|------|-------------------------|-----------|
| K-2A | 14" Tam., S18°E, 55.0' | 13 | 24" Balm, North, 7.9' | except 16 |
| | 8" Cedar, S60°E, 37.1' | | 20" Maple, S64°E, 30.1' | |
| | 24" Tam., S18°W, 82.7' | | 8" Balm, S60°E, 19.0' | |
| | 12" Tam., West, 37.1' | | 8" Maple, S45°W, 5.3' | |
| 16 | 1" pipe w/plastic cap buried in E-W Road. | 13-9 | 6" Cedar, N46°E, 3.2' | |
| | 5" Maple, S27°E, 37.95' | | 14" Cedar, N81°E, 19.3' | |
| | 10" Hemlock, South, 47.3' | | 8" Cedar, S2°E, 19.4' | |
| | 5" Maple, N23°W, 52.9' | | 10" Cedar, N68°W, 21.3' | |
| | 10" Maple, N16°E, 50.6' | | Edge of Lake 12' North | |

SIGNED BY Gerald L. Wiggins
Gerald L. Wiggins

DATE 9-11-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

