

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

MACKINAC CO.

4 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> R. <u>12</u> <sup>E.</sup> / <sub>W.</sub>	<u>E-6, J-8, K-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	, T. <u>43</u> <sup>N.</sup> / <sub>S.</sub> R. <u>12</u> <sup>E.</sup> / <sub>W.</sub>	<u>14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> / <sub>S.</sub> R. _____ <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-15, 6-25-85, 4-18, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-6 West 1/4 Corner of Section 16. OBT'S: Sugar 14", N12°W, 31 lks. & Sugar 26, S17°E, 28 lks.
- J-8 Center of Section 23. Not prev. set.
- K-2 1/4 Corner on East side of Section 2. OBT'S: Beech 18, S43°E 18 lks & Sugar 24, N62°W, 24 lks.
- 14 South 1/16 Corner on East side of Section 2. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-6 Corner set M.P.O.L. between NW and SW Section Corners of Section 16.
- J-8 Corner set at intersection of N-S and E-W 1/4 lines of Section 23 by closed traverse.
- K-2 Corner set at record distance from SE Cor. of Sec. 2 on a mean bearing between the West line of Sec. 2 and the East line of Sec. 1.
- 14 Corner set M.P.O.L. between East 1/4 Corner and S.E. Section Corner of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: DNR MONUMENTS.

- |     |                           |     |                        |
|-----|---------------------------|-----|------------------------|
| E-6 | 6" Cedar, S29°W, 41.3'    | K-2 | 6" Cedar, East, 9.9'   |
|     | 7" Spruce, S77°W, 11.2'   |     | 5" Cedar, S62°E, 4.6'  |
|     | 8" H. Maple, N49°E, 13.6' |     | 8" Cedar, S37°W, 12.0' |
|     | 8" Spruce, S60°E, 27.8'   |     | 6" Cedar, N60°W, 8.05' |
| J-8 | 8" Spruce, S45°E, 13.6'   | 14  | 5" Cedar, N66°E, 2.3'  |
|     | 6" Cedar, S45°W, 10.45'   |     | 5" Cedar, N33°E, 7.1'  |
|     | 7" Cedar, N36°W, 26.45'   |     | 8" Cedar, N3°E, 12.2'  |
|     | 12" Spruce, N67°E, 19.9'  |     | 8" Cedar, S22°E, 10.6' |

SIGNED BY

*Gerald L. Wiggins*  
Gerald L. Wiggins

DATE 9-11-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: