

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY
T 43N R 12W

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 12-13

CORNER MONUMENT and squared Cedar post

DATE MONUMENT PLACED AND WITNESSED 5-20-71

WITNESSES TO CORNER..... 8" Cedar (¼S NBT) S30°W 16.8'



10" Cedar (¼S NBT) N73°W 21.8'

10" Cedar (¼S NBT) N49°E 17.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner in original location from one Cedar bearing tree, N45°E, 17 links. Found this cedar, a stump 30" high with scribe marks and remains of the bottom blaze evident.

Found several blazes with signatures of timber cruisers, facing the corner. No evidence of the Spruce witness.

Corner lies on an old abandoned grade and 48' south of an other old abandoned grade. Corner location has been used for many years with blazed lines and cutting edges apparent.

Found a small wood picket at corner.

This corner located in a cedar swamp.

Found corner while making a survey to verify a section corner, ½ mile east of here.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

DATE

7-26-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing ✓

R 4047
Rev. 10/68