

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. R. <u>12</u> W.	K-8
2. PROPERTY CONTROLLING IN SECTION <u>24</u>	T. <u>43</u> N. R. <u>12</u> W.	10-Sec. 24 & 3-Sec. 24
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-23, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

K-8 Quarter Corner bet. Secs' 23-24, set by Guy Carlton D.S., in 1849. Bearings were: Cedar 6", S25°W, 08 lks. & Tam. 6", N15°E, 21 lks.

10-Sec. 24 South 1/16 Corner on West side of Section 24.

3-Sec. 24 North 1/16 Corner on West side of Section 24.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

K-8 Placed corner at a squared wood post, set by unknown surveyor.

10-Sec. 24 Placed corner at a squared wood post.

3-Sec. 24 Placed corner midway bet. sec. cor. to North and quarter corner to South.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminium cap at all corners. Bearings:


K-8 5" Cedar, S52°E, 10.8' & 9" Cedar, N56°E, 7.1' & 8" Cedar, S80°W, 24.2'.

10-Sec. 24 8" Hemlock, N71°E, 33.6' & 10" Hemlock, S52°E, 43.8' & 8" R. Maple, S60°W 6.1'.

3-Sec. 24 12" Cedar, N36°W, 8.1' & 14" Cedar, N20°E, 9.0' & 14" Cedar, S1°W, 5.5'.

SIGNED BY Billy D. Buckler  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 2-19-81



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_