

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co. 4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 N. R. 12 E.	I-8, I-6
2. PROPERTY CONTROLLING IN SECTION_____ 14	T. 43 N. R. 12 E.	3-Sec. 14, 10-Sec. 14
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-15 & 6-22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Quarter Corners set by Guy H. Carleton, D.S. in 1849. Bearings were:

I-8 1/4 Cor. bet. Sec's. 22-23; Spruce 8", S40°W, 10 lks. & Cedar 6", N61°E, 10 lks.
I-6 1/4 Cor. bet. Sec's. 14-15; Cedar 10", N39°W, 9 lks. & Aspen 24", N84°E, 5 lks.
3-Sec. 14 North 1/16 Corner on West side of Section 14.
10-Sec. 14 South 1/16 Corner on West side of Section 14.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-8 Placed corner at an old axle shaft, set in a fence line to East. Several old blazes but nothing original found.
I-6 Re-established corner midway and on line bet. two Sec. Corners. Found no evidence of original corner.
3-Sec. 14 Placed corner midway bet. Sec. Cor. to North and 1/4 Cor. to South.
10-Sec. 14 Placed corner midway bet. 1/4 Cor. to North and Sec. Cor. to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners. New bearings & bearings:

I-8 8" Cedar, N72°E, 17.8' & 8" Cedar, N5°E, 22.5' & 8" Cedar, S41°W, 18.5'.
I-6 8" Cedar, N45°W, 40.3' & 9" Cedar, S71°E, 37.9' & 8" Cedar, S1°E, 6.7'.
3-Sec. 14 7" H. Maple, S15°E, 72.8' & 9" H. Maple, N50°E, 54.7'.
10-Sec. 14 6" Cedar, West, 9.6' & 6" Cedar, S22°W, 14.7' & 8" Cedar, S62°E, 16.9'.

SIGNED BY

Billy D. Buckler
BILLY D. BUCKLER

DATE 6-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

