

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>12</u> E. R. <u>12</u> W.	<u>H-9</u>
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. <u>43</u> N. <u>12</u> E. R. <u>12</u> W.	<u>2, 10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-21 & 5-27, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-9 North 1/4 Corner of Section 27. OBT'S: Cedar 8, N45°W, 12 lks. & Cedar 10, S30°E, 8 lks.
- 2 East 1/16 Corner on North side of Section 27. Not previously set.
- 10 South 1/16 Corner on West side of Section 27. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-9 Corner set M.P.O.L. between N.E. Corner and N.W. Corner of Section 27. Corner lies east edge of trail road running north.
- 2 Corner set M.P.O.L. between North 1/4 Corner and N.E. Corner of Section 27.
- 10 Corner set at found 1" pipe. Distance North to 1/4 corner and South to Milakokia Lake fit record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-9 1" pipe with Plastic RLS Cap. Tags in Power Pole, N85°E, 63.0' & 4" Cedar, N32°E, 58.9' & 6" R. Pine, N66°W, 91.85' & Power Pole, N81°W, 175.35' & Center Line US#2, South, 83.0'.
- 2 1" pipe with Plastic RLS Cap. Power Pole, N83°W, 78.5' & 6" Cedar, N43°W, 41.5' & 8" Cedar, N36°E, 47.7' & 4" Maple, N61°E, 31.6' & Center Line US#2, South, 93.3'.
- 10 DNR Monument placed beside 1" Pipe. 12" W. Birch, West, 20.1' & 8" Maple, N12°W, 20.9' & 10" W. Birch, N16°E, 27.8' & 24" Twin Maple, N70°E, 15.2'.

SIGNED BY _____

Gerald L. Wiggins
Gerald L. Wiggins

DATE 9-8-87

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

23521

FOR STATE AND UNITED STATES AGENCIES: _____

