

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. S. R. <u>12</u> E. W.	<u>K-10, L-11</u>
2. PROPERTY CONTROLLING IN SECTION <u>26</u>	T. <u>43</u> N. S. R. <u>12</u> E. W.	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-21 & 6-2, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-10 East 1/4 Corner of Section 26. OBT'S: W. Birch 12, S35°W. 12 lks. & Aspen 12, N20°E, 15 lks.
- L-11 South 1/4 Corner of Section 25. OBT'S: Cedar 12, N5°E, 25 lks. & Cedar 14, S42°W, 12 lks.
- 7 North 1/16 Corner on East side of Section 26. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-10 Corner set at found axle shaft, measured distance South to stream fits record.
- L-11 Corner set M.P.O.L. between S.W. Corner and S.E. Corner of Section 25.
- 7 Corner set M.P.O.L. between N.E. Corner and East 1/4 Corner of Section 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-10 DNR at Axle Shaft. 14" Maple, N46°W, 35.8' & 10" Maple, N46°E, 13.4' & 16" Maple, S40°E, 29.5' & 14" Cedar, S35°E, 23.2'.
- L-11 DNR Monument. 4" Cedar, N63°E, 3.5' & 6" Cedar, S24°E, 13.45' & 7" Cedar, S30°W, 12.75' & 6" Cedar, N55°W, 0.5'.
- 7 DNR Monument. 6" Cedar, N38°W, 12.2' & 16" Cedar, East, 42.0' & 8" Cedar, S64°E, 29.3' & 6" Cedar, S45°W, 8.4' & 6" Sq. Balsam, S39°W, 2.5'.


SIGNED BY \_\_\_\_\_

*Gerald L. Wiggins*  
Gerald L. Wiggins

DATE 9-8-87

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

23521



FOR STATE AND UNITED STATES AGENCIES: