

**DATE SURVEY & REMONUMENTATION**

**MACKINAC COUNTY REMONUMENTATION CORNER**

MAY 20 1997

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**  
MACKINAC

**RECEIVED & FILED**  
DIANE FRAD KOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

NOV 10 1996  
AM PM  
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

Located In:	Corner Code #
(County)	
1. Public Land Survey	T <u>43N</u> R <u>12W</u> <u>M-6</u>
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2			1
3												
4	7	8			9		10		11			12
5												
6	18	17			16		15		14			13
7												
8	19	20			21		22		23			24
9												
10	30	29			28		27		26			25
11												
12	31	32			33		34		35			36
13												

I, JAMES H. GRANGER, in a field survey on October 2, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1841 - Original Survey Set wood post 20" Sugar S68°W 21 lks  
W. Burt 10" Sugar N58°W 21 lks
- 1980 - LCRC 1/2" Bar  
Thomas O'Brien # 21274
- 1989 - Survey 3/8" iron  
Neil Livasy # 31611
- 1993 - LCRC 1/2" iron  
Thomas Fabis # 31591

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron with cap # 31591 and four witnesses.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 8-30-96

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner **also corner A-6, T43N, R11W**

Set 5/8" X 30" rebar with Remonumentation Cap in Monument box

- 8" Maple S62°W 52.90' Fd. tag #31591
- 8" Ash S72°E 25.64' Fd. tag #31591
- P. Pole N40°E 65.08' Fd. tag #31591
- P. Pole N37°W 77.37' Fd. tag #31591



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date 10-10-96