

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>12W</u>	<u>C3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 15 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Corner common to Sections 5-6-7-8. 1973: Reestablished by J.L.Wilcox, RLS 14102 by double proportionate measurement. Set 1/2" iron. S45E 20.19' 4" Red Pine, N40E 22.69' 4" Red Pine, S80W 67.62' 12" dbl Maple.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Found and accepted the 1973 monument, in good condition and at record bearing and distance from the double Maple, now 14" DBH. The Red Pine NBTs were not recovered. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Found 1/2" rebar. Blazed, scribed, and set measuring nails in:
 14" twin Maple S77W 67.3' "S7 NBT"
 14" Spruce N82E 13.35' "S5 NBT"
 12" Spruce S39E 20.25' "S8 NBT"
 6" R.Pine N10W 36.8' "S6 NBT"
 Bearings are magnetic. Distances are to nail with tag.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3			●										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/17/04