

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 5 T 43N R 12W	4
	S 5 T 43N R 12W	5
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims

5	Oct 08 2003
4	Dec 15 2003

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2			
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (4-Sec. 5) Northwest 1/16 corner, Section 5. Not established in the original survey.
- (5-Sec. 5) North 1/16 corner, Section 5. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (4-Sec. 5) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (5-Sec. 5) Established the corner on the N-S 1/4 line 20 chains, proportionate to the protracted GLO record, north of the unmonumented intersection of 1/4 lines (D2). I proportioned using an overall all record dimension D1-D2 of 38.33 chains, being the mean of the GLO record on the East and West section lines. My distances north and south to D1 and D2 are 1312.60' and 1203.00', respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (4) Set 1" IDx36" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
6" W.Birch N65W 12.8' "NW1/16 8T"
8" Balsam S36E 12.9' do
5" Aspen S24E 29.55' do
6" W.Birch S68W 63.5' do | (5) Set 1" IDx36" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
5" Ironwood N27W 15.7' "N1/16 8T"
14" Balsam S20W 28.4' do
8" Maple S04E 25.3' do
5" Ironwood S37E 18.7' do |
| Bearings are magnetic. Distances are to nail with tag. | Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/17/04