

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Mackinac
 (County)

Located In: Corner Code #

1. Public Land Survey	T 43N R 12W	D1
	T 43N R 12W	D3
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

D3 Dec 15 2003
 D1 Oct 08 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D1) Quarter corner common to Section 5 T43N-R12W and Section 32 T44N-R12W. 1841: Established by Wm. A. Burt, DS: West on South side Section 32...40.00 Set qr Section post. Sugar 10 N72E 57, Sugar 16 N50W 22...80.00 Set post corner of Sections 31 & 32.
 (D3) Quarter corner common to Sections 5-8. 1849: Established by Guy H. Carleton: West corrected between Sections 5 and 8...40.05 Set post for 1/4 Sec. corner. Sugar 24 S20W 22, Sugar 10 N15W 23. 1973: Reestablished by Jerry L. Wilcox RLS 14102 as part of a large retracement survey in T43N-R12W and T44N-R12W. Set 1/2" iron and cap by single prop. S60W 16.41' 12" Red Pine, N05W 6.86' 8" Elm, S85E 6.91' 8" Elm.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D1) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners of record 2639.73' East and West.
 (D3) The original post, accessories, 1973 monument and accessories were not recovered. It appears that the physical evidence of the 1973 survey has been destroyed by logging operations. I reestablished the corner according to the 1973 method, midway and on a line of mean true bearing between Section corners 2633.42' East and West (sketches provided by Wilcox Assoc., Inc. show a 1973 measure of 5281.11' from C3 to E3, 14.3' longer than I found it to be). Found a wood post for an approximate corner about 5 ft. north of the reestablished position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D1) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 12" Maple N74W 7.55' "1/4S NBT" 8" Maple N78E 12.0' do 10" Maple N15W 5.9' do 6" Maple S50E 12.85' do Placed cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(D3) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 6" Balsam N32W 10.7' "1/4S NBT" 8" Balsam N35E 19.65' do 10" Cedar in clump S23E 78.8' do 5" twin Cedar S57W 64.65' do Bearings are magnetic. Distances are to nail with tag.
--	---

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/17/04

For the Michigan Department of Natural Resources, Office of Land and Facilities