

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for 'For corners in Mackinac (County)', 'Located In:', 'Corner Code #', and numbered sections 1-5 for survey details.

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 07 1993
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

Neil E. Hill, in a field survey on October 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: Established by Austin Burt, in the original government survey of the range line T43N, R02-03W. Set wooden post and established the following references: 8" Fir S40W 19Links 8" Fir N65W 38Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1986: ECI, no original corner evidence recovered. Found potential stump hole N65W 26.5', more or less, under still rooted 19" Balsam Fir; positive identification impossible. Corner position established at the intersection of ancient fence line to the North and West. According to the land owner, Mr. John Feffers, the fence was erected prior to 1920 with his help and was apparently feet on the Section line. This corner position agrees closely to adjacent corners in regards to alignment and proportioned G.L.O. distances.

1986: Alan K. Pierce, L.S. #30097, set a 2-1/2" O.D. x 4' long galvanized iron pipe with a plastic flanged base and capped with a 3-1/4" bronze tablet stamped to identify the corner. Bearing trees are blazed scribed, painted and tagged with distances being measured from an aluminum nail in the side of the tree. 10" Balsam Poplar N43E 46.18' 5" Balsam Fir West 59.48' 14" W. Spruce S79E 105.64' 22" H. Maple N27W 119.07' Post North 2.5'


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Found a 2-1/2" O.D. iron pipe capped with a 3-1/4" bronze tablet stamped to identify the corner. Witnesses located in the NE Corner of open field with woods East & North. Bearing trees are blazed, scribed, painted and tagged, with distances being measured from an aluminum nail in the side of the tree.

10" Balsam Poplar N43E 46.18' 5" Balsam Fir West 59.48' 14" W. Spruce S79E 105.64' 22" H. Maple N27W 119.07' Post North 2.5'

1993: Upon review, the location and witnesses for the corner as recorded in Liber C-128 (Corner Records), are sufficient to perpetuate corner location.

Signed by Neil E. Hill 27447 P.S., P.C. Date October 15, 1993
Surveyor's Michigan License No. Remonumentation Surveyor



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

D-0225