

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

- | | | | | |
|------------------------------------|---|-------------|-----------|------------|
| 1. Public Land Survey | T | <u>43NR</u> | <u>2W</u> | <u>A-5</u> |
| | T | _____ | _____ | _____ |
| | T | _____ | _____ | _____ |
| | T | _____ | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | _____ | _____ |
| | S | _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | _____ | _____ |
| | S | _____ | _____ | _____ |

RECEIVED & FILED
DIANE FRANK KOVACH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 07 1993

AM _____ PM _____
7[8]9[10]11[12]13[14]15[16]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Neil E. Hill

October 1 93

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: Established by Austin Burt, in the original government survey of the range line T43N R02-03W.
Set a wooden post and established the following references:
8" Birch S05W 15 Links 10" Basswood N31W 8 Link
- 1845: Established by James Mullet in the original Government subdivision of T43N, R20
Witnessed the original post with:
10" Fir N53E 13 Links 15" Spruce S52E 21 Link
- 1960's: M.D.O.T., corner not specified
12" Balsam poplar S28W 11.66 feet 8" Balsam N36E 11.29 feet
8" Balsam N09E 28.47 feet 8" Balsam N60W 10.25 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1986: ECI, no original corner evidence recovered. Rejected calculated M.D.O.T. position based upon non-conformance with G.L.O. feature calls. Corner position established at single proportionate distance on line between the first M.C. South of the NE Corner of Section 12 and the first M.C. North of the E-1/4 of Section 13. Measurements taken from this corner agree reasonably with record G.L.O. dimensions as follows:
- R.H. bank of Pine River to the West (521.6'-ECI; 541.2'-G.L.O.)
- Corner Section 11, 12, 13, 14, T43N, R3W, (5295.5'-ECI; 5293.2'-G.L.O.)
- 3 Link wide stream to South (780', more or less, -ECI: 785.4'-G.L.O.)
- 1986: Alan K. Pierce, L.S. #30097, set a 2-1/2" O.D. x 4' long galvanized iron pipe with plastic flanged base and capped with a 3-1/4" bronze tablet stamped to identify the corner. Bearing trees are blazed, scribed, painted and tagged with distances being measured from an aluminum nail in the side of the tree. 10" Balsam Poplar-S35W 20.50' Post-North 4.00' 10" Aspen-S51E 24.00' 14" Oak-N01E 7.42' 8" Balsam Poplar-N39W 48.22'


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Found a 2-1/2" O.D. galvanized iron pipe capped with a 3-1/4" bronze tablet stamped to identify the corner. Also found the following witnesses, of which bearing trees are blazed scribed, painted and tagged with distances being measured from an aluminum nail in the side of the tree.
14" Oak N01E 7.42 feet 10" Aspen S51E 24.00 feet
18" Balsam Poplar S35W 20.50 feet Post North 4.00 feet
8" Balsam Poplar N39W 48.22 feet - (broken off at 8 feet)
- 1993: Upon review, the location and witnesses for the corner as recorded in Liber C-13 (Corner Records), are sufficient to perpetuate corner location.

Signed by Neil E. Hill P.S. P.C.

Surveyor's Michigan License No. 27447

Remonumentation Surveyor
D-0228



October 15, 1993

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983