

1993

1993 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Mackinac
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>2W</u>	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED & FILED
CLARK COUNTY REGISTER
MACKINAC COUNTY

OCT 28 1993

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie, in a field survey on June 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845: Established by J.H. Mullett, G.L.O. Survey
Set a wood post and referenced
10" Fir - N84°E - 11 Links
10" Birch - N87°W - 21 Links

1987: Survey by Richard L. Hays of Nordlund & Assoc. for U.S. Forest Service.
1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found a 2½" x 3' aluminum monument with a 3" aluminum cap stamped to identify the corner. Set in 1989 by Richard L. Hays P.S. No. 25847 by single proportionate measurement between the Northeast and Southeast Corners of Section 6. Recorded November 27, 1989. (Book D, page 27)

Plat of Survey Recorded as U.S. Gov't. Plat of Survey No. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: West - 0.61 feet - (R= 0.70') - Steel Post
N84°E - 31.05 feet - (R= 31.00') - 9" Maple
N35°W - 49.08 feet - 14" Spruce
S72°W - 34.00 feet - (R= 34.05') - 10" Maple
S22°E - 46.98 feet - 9" Maple

(Tree references are blazed and tagged.)

The monument is a 2½"x3' aluminum monument with a 3" aluminum cap stamped to identify the corner.



Signed by David B. Guthrie Date 9/27/93
Surveyor's Michigan License No. 22435