1993

1993: Mackinac County Remonumentation Corner


LAND CORNER RECORDATION CERTIFICATE

COMMISSION

For corners in Mackinac		Fining Nequirement of Act 14, which F.A. 1910		
		Located In:	Corner Code ##	RESERVE & FARD
1.	(County) Public Land Survey	T43N_B 2W	C-4	MACHER FOR THE CONTROLS MACHER FOR SHAPER FOR CONTROLS
••	. dono Lana ourto,	T R T R		OCT 28 1995 AM PM 7181911411414141516
2.	Property Controlling in Section	S T R S T R		i kofatrotaat mirahasasasa
3.	Miscellaneous Property in Sec.	S T R S T R		Register of Deeds Stamp & File Number

I, <u>David B. Guthrie</u> in a field survey on <u>June 10</u>, 19 <u>93</u>, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

1845: Established by J.H. Mullett, G.L.O Survey Set a wood post and referenced

8" Fir - S82°E - 6 Links 10" Sugar - S30°W - 8 Links

____ , Recorded Plat _

Private Claims

1987: Survey by Richard L. Hays of Nordlund & Assoc. for U.S. Forest Service.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found a 2½" x 3' aluminum monument with a 3" aluminum cap stamped to identify the corner. This corner was set in 1989 by Richard L. Hays, P.S. No. 25847, by single proportionate measurement between the Northeast and Southeast corners of Section 7. The corner was recorded November 30, 1989. (Book D, page 44)

Plat of Survey Recorded as U.S. Gov't. Plat of Survey No. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: N48°W - 43.28 feet - (R=43.25') - 6" Ash S31°W - 46.53 feet - 6" Spruce S74°E - 93.62 feet - 8" Spruce S66°W - 12.88 feet - 4" Spruce North - '2.60 feet - Steel Post

(Tree references are blazed and tagged)

The monument is a $2\frac{1}{2}$ "x3' aluminum monument with a 3" aluminum cap stamped to identify the corner.



Signed by Will talk

Date Sist. 27, 1593

Surveyor's Michigan License No. 22435

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971