

1993

1993 Mackinac County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Mackinac
(County)

Located In: Corner Code #

- 1. Public Land Survey T 43N R 2W E-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

RECEIVED & FILED
DIANE E. JOHNSON
MACKINAC COUNTY REGISTER OF DEEDS

OCT 28 1995
AM PM
71810101-1-1-1301816

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie, in a field survey on June 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: Established by William A. Burt, G.L.O. Survey. Set 10" White Birch-
No references.
 - 1845: Survey by J.H. Mullett.
 - 1971: Survey by Mary C. Feindt.
 - 1987: Survey by Richard L. Hays of Nordlund & Assoc. for U.S. Forest Service.
 - 1989

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1993: Found 2 1/2" x 3' aluminum monument with a 3" aluminum cap stamped to identify the corner. Set in 1987 by Richard L. Hays to replace a 1 1/2" Well Point previously set by Ray Walker. (MDOT) 1987 corner by Richard L. Hays P.S. No. 25847 recorded December 9, 1988. (Book C, page 354)
This corner lies in the ditch on the easterly side of the north, south road.
Plat of Survey Recorded as U.S. Gov't. Plat of Survey No. 14.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1993: S80°E - 38.72 feet - 8" Wild Cherry
N80°E - 37.98 feet - (R= 38.03') - 8" Wild Cherry
N69°W - 58.71 feet - (R= 58.70') - 12" Wild Cherry
S61°W - (R=S91°W) - 95.65 Feet - 6" Wild Cherry
S15°W - 35.00 feet - 6" Spruce
East - 1.65 feet - Steel Post
(Tree references are blazed and tagged.)
The monument is a 2 1/2"x3' aluminum monument with a 3" aluminum cap stamped to identify the corner.



Signed by D.B. Guthrie Date Sept. 27, 1995
Surveyor's Michigan License No. 22435